

Please contact us if you meet any problems in implementing these instructions.

Technical contact person :

Stephane ABRIOUX +33 6 64 25 32 10 - [pourdevrai@lafaussecompagnie.fr](mailto:pourdevrai@lafaussecompagnie.fr)

Artistic contact person :

Thomas LE SAULNIER +33 (0)6 74 75 52 74 - [pourdevrai@lafaussecompagnie.fr](mailto:pourdevrai@lafaussecompagnie.fr)

*The VibratO show takes place around and inside the Kiosk. It can be set up in a community area: a place where people pass through. The Kiosk is also a piece of street furniture open to the public. It remains accessible outside performance times, including at night. The public can move around and inside the installation.*

**The Kiosk is a OP2 type structure covered by the guide on dismantlable sets and structures. The APAVE periodic inspection report dated August 2019 is included with this technical sheet.**

## Location and layout of the kiosk



### Location

Depending on the venue, it may be necessary to plan a prior visit to the site for the artistic and technical team (2 people) to discuss the installation area and the various VibratO events with the organiser. This will be arranged by mutual agreement between the two parties, with the organiser paying the costs involved (transport and, if necessary, accommodation).

### Set-up (see plan page 2)

- an unencumbered assembly area accessible by truck and trailer (13 m convoy)
- flat ground (incline allowed: less than 2%),
- stable ground is essential (see load bearing capacity table on page 2)
- options for bracing: tent clamps (provided by the company), ballast (to be provided), trees, etc.
- shade preferable in spring and summer

Site plan



SUMMARY TABLE OF MAXIMUM LOAD DISTRIBUTION PER FOOT  
Unit of measurement: metric ton

POINT	PERMANENT LOAD	LIVE LOAD	TOTAL
1	0,23	0,37	0,60
2	0,27	0,56	0,83
3	0,27	0,55	0,82
4	0,39	0,66	1,05
5	0,40	0,66	1,06
6	0,30	0,67	0,97
7	0,28	0,65	0,93
8	0,32	0,53	0,85

## Timetable

**2 days before the show:** Arrival around 7 pm (if more than 3 hours' drive)

**The day before the show:** Set-up (6 hours)

**Performance period:** 2 consecutive days minimum

**Day after the show:** Dismantling (4 hours)

No assembly and dismantling at night. In winter, sufficient lighting needs to be provided for the site during set-up and dismantling if this takes place in the late afternoon.

In the event of exceptional weather conditions, set-up and performances may be postponed.

## To be provided by the organiser

### Staff

- 2 people to help with set-up (the day before) for the first 4 hours and dismantling (the day after) for 3 hours (qualified staff appreciated).

Access to a power supply is needed for assembly.

- 2 people to help with the transformations of the Kiosk during the performance period (installation and removal of the handrails, removal of terraces) - 1 hour per transformation - availability to be defined according to the order of artistic events during the day.

- 1 person to supervise the site during mealtimes on assembly and dismantling days. Depending on the event, it may be necessary to guard the structure at night, but without prohibiting access to it.

### Power

2 x 16A lines, with a good earth and, if necessary, cable runs from the Kiosk to the power supply source.

### Equipment required throughout the performance period

- 2 AB type fire extinguishers
- 8 crowd control barriers and flagging tape for set-up and dismantling times (if the set-up zone is in a busy area)

We provide load distribution chocks for a compact lawn. If the type of ground is different or less compact, the organiser must provide us with extra chocks.

The artists set up their «camp» close to the Kiosk with a small brazier (20 cm diameter) on a tripod).

## Transport

The convoy consists of 2 wheeled entities (vehicles + trailers).

One Iveco 35C15 truck (rental) with the Kiosk trailer (EN-883-YY)

Total length of convoy: 13.5m

Kiosk trailer measurements:

width: 2.25 m

height: 2.35 m

length (with tongue): 5.95 m

weight: 2.8 mt

One Renault Trafic van (CN-210-CB) with luggage trailer (FE-720-ZV)

Total length of convoy: 9.5 m

Luggage trailer measurements:

width: 1.38 m

height: 1.60 m

length (with tongue): 3 m

weight: 750 kg

A secure parking area will be needed for both convoys the night before assembly.

During the event, provide parking for the Iveco 35C15 truck and luggage trailer near the performance area.

The Kiosk trailer is used as the base for the Kiosk structure, so the set-up area needs to be accessible to the 13.50 m convoy.

With indoor installations, the Kiosk trailer must be able to pass through the entrance.

A smooth floor will make it easier to handle the trailer by hand (at least 6 people are required).

